

# Phase II Collimators: design status

LHC Collimation
Working Group

24<sup>th</sup> August, 2009

A. Dallocchio, A. Bertarelli

on behalf of the Phase II Collimation design team



## Design Baseline (sol. 2)

Sol. 2 finally chosen (12<sup>th</sup> CDM2 May 2009): equipped jaw (3 sectors) with 2 intermediate adjustable supports to obtain best geometrical stability.

Fine adjustment system

Cut jaw: each piece is independently supported on the back stiffener.

Enhanced geometrical stability


Mo Back - Stiffener RF contacts ensure electrical conductivity between jaw pieces

Preliminary FEM estimation: 50÷60µm with GlidCop jaw in nominal condition.

A. Dallocchio, A. Bertarelli

**LHC Collimation Working Group** 


24/08/2009





### **Alternative Materials**

Modular design approach allows the choice of different materials for the collimator jaws: Metal jaw vs. Ceramic jaw... (waiting for further specifications)






#### Mechanical design

- Preliminary design study of the jaw assembly completed.
- Drawing folder (60 drawings) provided to main workshop for cost estimation, delivery time for production of a full prototype and possible design optimization (Mo vs. INOX back-stiffener depending on costs/benefits).
- Prototype of Phase II moving tables (linear shaft ball bearings).
   successfully tested 24.000 cycles. New Endurance test ongoing.
- Cooler prototypes so far successfully tested (final tests ongoing).

#### Materials R&D and calculations

- Cu-CD and SiC samples under characterization.
- Waiting for new FLUKA results for in-depth thermo-mechanical analysis and possible design optimization.
- FP7 collaboration started with Polito and GSI for hydrodynamic simulations.





- Preliminary test in the lab. with the wire gave positive results.
- Further tests with motorized jaws will be completed by BE-BI within week 36-37. (Please ask us within the end of this week for any other test required).
- Prototype will be dismounted in week 38 and prepared for future installation in the SPS LSS5 (4-5 week activities in the workshop).
- SPS technical stop of 02-Nov-09 will be exploited by EN-STI to uninstall Proto 1 and install adapted LHC support with vacuum chamber (including cabling and water connection).
  - Waiting for RP green light and availability of VSC group.
  - BE-BI is checking the availability of BPM cables for the SPS.
  - Official documents (ECR...) to be prepared
  - Is a presentation of planned activities necessary at IEFC? (Ralph)