Orbit feedback for collimation

J. Wenninger AB Operation / SPS

- Requirements on orbit stability
- Expected orbit perturbations
- Feedback architecture
- Feedback tests at the SPS
- Collimation setup issues
- Summary

Acknowledgements : R. Assmann, R. Jones, M. Lamont, R. Schmidt, R. Steinhagen

The core team

AB operations group : accelerator physics, architecture, prototype tests

Jorg Wenninger	10-20%
Ralph Steinhagen (doct. student)	~100%

AB beam diagnostics group : BPM system

Rhodri Jones

Lars Jensen

AB controls group : architecture, control issues

Jens Andersson (fellow)

has left CERN

+ colleagues of AB and AT department, collimation and machine protection WG.

The role of the orbit feedback

Two distinct steps for orbit correction & stabilization

1. Establish a reference orbit

- More or less manual corrections to define a reference orbit.
- Established by the operation crews using applications embedded in the LHC controls system (LSA, presentation by M. Lamont). Responsible for steering application is J. Wenninger.

2. Stabilize the orbit

- Stabilize the orbit around the pre-defined reference.
- This is the role of the orbit feedback.



Local stability requirements

Absorbers & protection devices :

TCDQ (prot. asynchronous beam dumps)	<0.5 σ	IR6
Injection collimators & absorbers	~0.3 σ	IR2,IR8
 Tertiary collimators for collisions 	iary collimators for collisions \sim 0.2 σ	
ightarrow absolute numbers are in the range :	~100-200 μm	
Active systems :		
 Transverse damper 	~ 200 μm	IR4
Q-meter / PLL BPM	~200 μm	IR4
Performance :		
 Collision points stability 	minimize drifts	IR1,2,5,8
TOTEM / ATLAS Lumi Roman Pots	~20 μm	IR1,IR5

Global stability requirements

Injection protection :

• Arc aperture wrt protection devices $<0.5\sigma \sim 0.5$ mm

Feed-down of multipoles (injection/ snapback) :

Reduce perturbations from feed-downs
 <0.5 mm

Electron cloud :

Maintain beam on cleaned surface
 <1 mm (?)

In summary :

- Many tight local requirements
- Looser global requirements
- Collimation is the driving constraint behind the feedback system.
- Collimation constraints of ~ 50 μm may become tighter if the β -beat changes are larger than 5% !

Sources of orbit perturbations

Ground motion :

- LEP experience predicts slow drifts ~ 200-500 μ m / store.
- No problems expected at frequencies > 0.5 Hz.

Dynamic effects from superconducting magnets (injection, ramp start) :

Induce few mm rms drifts, dominated by random b1.

Beta squeeze :

- Most critical source of perturbations, amplitudes of up to 20 mm !
- Depends critically on orbit quality in insertions and alignment.
- Use feed-forward from cycle to cycle to reduce effects.

Other sources :

Ramp...

Orbit feedback and operation

For nominal performance the orbit tolerances are very tight.

- The relative position of collimators, absorbers.. must be maintained throughout the LHC cycle.
- The orbit is not a 'play-parameter' for operation, except at low intensity.
 'Playing' with the orbit will result in guasi-immediate guench at high intensity.

At the LHC the orbit must always be very well controlled, but perturbations during various phases (snapback, ramp, squeeze) can be large and fast.

Stabilization by a <u>real-time orbit feedback</u> system was foreseen already at an early stage.

BPM system overview

- 528 BPMs/ring provide horizontal and vertical position measurements.
- Orbit sampling :
 - One BPM at each quadrupole
 - In the collimation sections, there is one BPM on each side of the quadrupole.
 - In the arcs the phase advance between BPMs is 45° sampling is good.
- BPMs are grouped into 64 acquisition crates.
 - 8 crates / IR.
- Acquisition based on 'Wide Band Time Normalizer' principle (CERN design) :
 - Position information is transformed into time duration.
 - Full bunch-by-bunch acquisition (40 MHz system).
 - RT orbit sampling at 10 Hz nominal frequency, possibly up to 25 Hz.
 - Orbit resolution < 5 μ m for nominal intensity.

Steering magnets

- There are ~280 orbit corrector magnets per ring and per plane.
- Most of the correctors are superconducting magnets :
 - Circuit time constants $\tau = L/R \approx 10$ to 200 s \rightarrow slow !!!
 - EVEN for SMALL signals, the PC bandwidth is ~1 Hz.
 At 7 TeV : ~ 20 μm oscillation / corrector @ 1 Hz.
- Much faster normal-conducting correctors are installed in IR3 and IR7.
 - Not usable for fast FB because they are too few of them.
- The PCs are connected over a real-time field-bus (WorldFip) to the gateways that control them – the bus operation is limited to <u>50 Hz</u>.

Consequence of BPM and PC system parameters :

The orbit FB could operate at up to 50 Hz - more likely at 10-25 Hz.

But this sampling rate is adequate given the expected perturbations !

Feedback architecture / 1

Local

- ✓ reduced # of connections.
- ✓ numerical processing simpler.
- ✓ ...

×

- × less flexibility.
- × not ideal for global corrections.
- × coupling between loops is an issue.
- × problems to ensure closure.

<u>Central</u>

- entire information available.
- \checkmark all options possible.
- ✓ can be easily configured and adapted.

\checkmark

×communication more critical – DELAYS !
 × large # of connections.

× ...

All light sources are moving into this direction



Feedback architecture / 2

Present baseline : central architecture

- Fully digital feedback.
- Centralized control with high performance (multi-processor) PCs running Lynx / Linux real-time operating systems.
- Correction based on a super-position of global and local corrections.

Global orbit correction using Singular Value Decomposition.

Local orbit corrections applied on top of the predicted global correction residual.

 \rightarrow both can be combined into a single matrix multiplication.

- Max. operation frequency is estimated to be ~ 25 Hz adequate.
- Combined stabilization of both rings possible.

Remark :

■ Because this design is flexible, it is possible to build fast local systems in selected IRs combined with a slow global loop → but this raises loop coupling issues.

Feedback Control Layout

Database settings, operation, users

Central FB unit has 2 functional parts

- Time-critical controller unit to compute the corrections (hard real-time).
- A Service Unit for DB and user interfaces, matrix operations, sanity checks..

The total loop delay is expected to be stable at ~ 60-80 ms



Technical network

The feedback will use the CERN Technical Network for data communication :

- Switched network
 - no data collisions
 - no data loss
- Very fast switches (delay ~ 3 μs)
- Double (triple) redundancy
- Transmission delays ~ 300 μs
 20% due to routers/switches
 80% propagation speed in optical fibres
- Provides QoS (Quality of Service) at the hardware level :
 - Feedback packets will have higher priority than other users.
 - 'Nearly' deterministic response delays negligible on FB time scale.
- We have performed numerous network tests for the FB, and they all showed that the network itself is not a problem. Network delays are smaller than 1 ms.



SPS prototyping

A feedback loop was sent up at the SPS and tested in 2003/2004 :

- 6 dedicated BPMs equipped with standard LHC electronics.
- Standard SPS CODs used as steering magnets (~14 Hz bandwidth).
- Data transport to the control room and back using the CERN technical network.
 Between 2003 and 2004 the SPS network was upgraded to the same hardware that is used for the LHC.



→ test LHC architecture and components

Prototype results / 2004



10.06.2005

LHC MAC / Orbit FB for Collimation / J. Wenninger

SPS collimator tests

• Scraping of up to $5_{-}10^{12}$ p at 270 GeV.

- No effect observed on downstream BPMs and overall orbit feedback – but no clear conclusion since the expected amount of beam loss is not known.
- Beam loss rates with orbit FB ON and OFF :
 - Increased noise observed on BLM signal, equivalent to noise of few μ m jaw steps.
 - Consistent with BPM noise.
 - Confirms ~ sub-micron stability of SPS beam at 270 GeV on time scale of seconds to minutes as expected from ground motion measurements.



Orbit stabilization for collimation / 1

The SPS tests and simulations gives us confidence that

- The baseline feedback architecture works,
- The stabilization requirements can be met,
- In particular stabilization better than 50 μm can be achieved in IR3 and IR7 for '*perfect' BPMs*,

but it is clear that the BPM data quality is absolutely essential to fulfil the local collimation requirements !

BPM bunch length dependence

Some residual bunch length effects are expected from the design.

- SPS tests demonstrate the effect up to ~ 200 μ m.
- Effect expected to be significantly reduced at the LHC.
 Filters are optimized for shorter bunch lengths
- Mostly a problem to compare injection & collision settings.
- BPM-to-BPM spread.
- Possibility to measure and correct if it is required...?







LHC MAC / Orbit FB for Collimation / J. Wenninger

SPS RF Voltage

BPM intensity dependence

- The LHC BPM electronics is only sensitive to the *bunch intensity*, but not to the total beam intensity or bunch pattern because it is intrinsically working on a bunch-by-bunch basis.
- Collimator setting up may be done with a few bunches, provided the bunch intensity is the same as for nominal fill.
- We have to expect some systematic effects as the intensity decreases.



Collimation setup

• Step 1 :

- Optimize collimators with a few bunches, but with the same bunch population as for normal fills (within ~10-20%).
- Record the orbit and define this orbit as reference.
- Step 2 :
 - Restore collimator positions and reference orbit (with FB) around the collimators for subsequent physics fills, making sure the bunch intensity is the same.

 \rightarrow Based on the SPS experience, this procedure should provide a reproducibility of better than 50 μ m.

Remark :

Detailed setup procedures are studied in the collimation project.

- Issues :
 - Systematic effect due to intensity decrease in physics requires some learning.
 - Long(er) term stability of the reference positions (orbit & collimators).

Summary

- The design of the LHC orbit FB is well advanced, including control aspects.
 - Implementation of the system to begin soon !
- Feedback tests have been performed in 2003 and 2004 at the SPS using BPMs equipped with LHC electronics.
 - The performance results exceeded our initial expectations, stabilization < 10 μ m achieved.
 - The new CERN networks for the SPS/LHC proved very reliable.
 - BPM reproducibility ~ 20-50 μ m over 1-2 days.
- Orbit reproducibility in the collimation region of better than 50 μm can be expected provided care is taken to ensure consistent bunch intensities.
 - Some systematic intensity dependent effects still need to be evaluated.
- (Possible) future SPS beam tests :
 - Reproducibility tests (BPMs collimator) time consuming !
 - BPM systematic effects.
- Impact of BPM/COD failures on FB : evaluation in progress...

Reserve slides

Machine apertures at injection

Mech. aperture of LHC ring defines the scale

→ tight aperture

Protection devices protect ring aperture

➔ protect against injected beam

Secondary collimators tighter than protection

ightarrow limit the amount of halo hitting protection devices

Primary collimators tighter than secondary

primary collimators define the aperture bottleneck in the LHC for cleaning of the circulating beam!

These conditions must always be fulfilled :

→ orbit tolerances are at the level of $0.1-0.5\sigma \approx 100-500 \ \mu m$.

! long distance correlations : some objects are separated by kms !

 The aperture definition includes tolerances for beta-beat (20%), orbit (4 mm), energy offsets, spurious dispersion...

 $a_{ring} \approx 8\sigma$



 $a_{sec} < a_{prot}$



$$a_{prim} \approx 5-6\sigma < a_{sec}$$

Machine aperture at 7 TeV

Settings at 7 TeV for fully squeezed beams ($\beta^* = 0.5$ m IR1/5)



 \rightarrow orbit tolerance around collimators is in the range $\sigma/3 \sim 50 \ \mu m$.

Ground motion

The LHC tunnel is a fortunately a quiet place...

orbit rms ≈ κ × ground movement
→ Uncorrelated motion : κ ≈ 35
→ Ground waves :

f < 5 Hz
κ ≈ 0 - coherent motion
f > 5 Hz
1 < κ < 100

orbits movements at f > 0.1 Hz are expected to be \leq 20 μ m !

Long term orbit drifts (LEP) : ~ 200-500 μm rms over a few hours ~ 20-50 μm rms over ~ minute(s)

→ a priori we expect similar figures for the LHC !





Beam data



10.06.2005

LEP slow orbit drifts

The measured slow LEP orbit drifts should give a good indication of what to expected at the LHC

 \rightarrow no problem for a FB running at \geq 0.5 Hz



10.06.2005

LHC MAC / Orbit FB for Collimation / J. Wenninger

LHC Amplitude to Time Normaliser Principle



LHC MAC / Orbit FB for Collimation / J. Wenninger

Wide Band Time Normalizer



Beam Position Data Rates

- Both rings covered by 1056 BPMs
- Measurement for both planes (2112 readings)
- BPM are organised in front-end crates (PowerPC/VME) in surface buildings \blacklozenge
 - 18 BPMs (hor & vert) → 36 positions / VME crate
 - 64 crates in total. 8 crates /IR

Data stream:

- Average data rates :
 - 18 BPMs x 20 bytes 1056 BPMs x 20 bytes \sim 21 kbytes
 - @ 25 Hz
- ~ 400 bvtes / sample / crate
 - / sample
 - ~ 4.2 Mbit/s + protocol overhead
- Achievable peak rates (bursts): 100Mbit/s resp. 1Gbit/s (depending on Ethernet interface) \blacklozenge



Feedback delays

- The total delay determines actual bandwidth and performance.
- Delays are inevitable and part of digital control systems. Some sub-systems that contribute to the loop delay:
 - Beam Position Monitor System :

	acquisition (255 turns@	∮f _{rev} ~11kHz)	~	10 ms		
	processing and sending	g	~	5 ms)	
	technical network		<	1 ms		
Fee	edback Control :					
	network inbound	(100 MBit/s)	~	3 ms		
	data processing (esser	ntially matrix multiplication)	~	15 ms	}	~ 30 m
	network outbound		~	3 ms		
	technical network		<	1 ms		
PC	System :					
	network inbound		~	3 ms		
	WorldFIP (50 Hz) clock	۲	- 20)-40 ms		

Total

~ 60-80 ms



FB proto-type at the SPS

Steering example with external noise over one SPS cycle, pulsed mode, FB running at <u>100 Hz</u>.



Prototype results / 2003

Feedback tests demonstrated good performance

- Stabilised the beam at 4 BPMs.
- Max. feedback sampling frequency 100 Hz.
- Position stabilization to 8.5 μm.



LHC MAC / Orbit FB for Collimation / J. Wenninger

The orbit FB 'Test-bed'

The test-bed is a complement to the Orbit Feedback Controller :

- Simulates the orbit response of COD → BEAM → BPM
 Includes the correct dynamic behaviour of the PC + magnet circuit.
- Same data delivery mechanism & encoding as in the real front-end Transparent for the FB system → simple "offline" debugging.
- Feedback performance can be tested and validated under various scenarios with the test-bed.



10.06.2005

Ground motion correction in collision

- "Reasonably conservative" global correction strategy.
 - \sim rather insensitive to isolated faulty BPMs.
- Decouple rings (i.e. common beam pipe elements not used).



Residual orbit shifts after ~ few hours of coast / 1 beam

Note the large residual drift @ IP1 despite a 100 x smaller $\beta \Leftrightarrow$ correction strategy !

10.06.2005

Simulation of squeeze

- Achievable residual orbit shift due to the squeeze using <u>ONLY</u> a global correction.
- A local correction can provide a 'perfect' correction because the perturbation in IR7 is basically a free betatron oscillation propagating into the collimation IR.



Conditions :

- Initial orbit rms 1 mm. (before squeeze)
- Misalignment rms 0.5 mm.

More eigenvalues for Singular Value Decomposition ↔ more aggressive correction

10.06.2005

LHC MAC / Orbit FB for Collimation / J. Wenninger

Influence of β -beating on correction

Orbit rms reduction (rms after / rms before) as a function of the β -beat (plots indicate ~ 2 x rms beating ~ peak β -beat) for a correction based on the NOMINAL optics.

 \rightarrow convergence is maintained up to peak β -beat of ~ 50%



increasing number of eigenvalues (SVD correction) \rightarrow more aggressive (and risky) correction

10.06.2005

LHC MAC / Orbit FB for Collimation / J. Wenninger