


Status of CCC applications for the Roman pot controls

S. Redaelli, AB-OP

with M. Dutour, S. Ravat, I. Atanassov

Acknowledgments: M. Lamont, P. Palazzi + TOTEM controls teams






Outline

- Introduction**
- Results of integration tests**
- Status of CCC applications**
- Conclusions**

Introduction

Collimator top-level controls architecture

Top-level (LSA)




Middleware (FESA)

OP provides the **top-level applications** for the Roman pot controls from the CCC.

In particular:

- Movements performed by the OP crew from the CCC following TOTEM requests
- Definition of **operational windows** for RP movements
- Application for RP alignment based on BLM reading, to have procedure comparable to collimators
- Handling of settings

We agreed on the FESA interface to control the **Roman pots** with the applications developed for the **LHC collimators**.



Specs of FESA interface



LHC Project Document No.
LHC-TC-ES-0002 rev 2.0

CERN Div./Group or Supplier/Contractor Document No.
AB-OP

EDMS Document No.
934341

Date: 2008-07-25

Engineering Specification

MIDDLE-LEVEL INTERFACE TO CONTROL MOVABLE DEVICES LIKE LHC COLLIMATORS

Abstract

This document describes the interface between the collimator middleware controls and the application for the collimator control from the control room. This interface is proposed as an easy way to extend the applications developed within the LHC Application Software (LSA) for the LHC collimator control to other movable devices. In particular, the cases of the beam dump diluter (TCDQ) and of the TOTEM Roman pots are considered in some details.

Prepared by:
S. Redaelli,
A. Masi

Checked by:
R. Bailey, C. Boucly,
E. Carlier, M. Deile,
M. Donze, M.P. Dutour,
B. Goddard, M. Jonker,
E. Radermacher,
F. Lucas Rodriguez,
J. Wenninger

Approved by:
R. Assmann,
P. Collier,
M. Lamont,
R. Losito

Definition of a minimum set of properties (summer 2008) that allow **plugging-in** the existing collimator applications onto the Roman pot middle-ware:


- (1) requested positions;
- (2) limit functions;
- (3) measured positions;
- (4) machine states, error, warnings;
- (5) stop bottom.

Development by M. Dutour, who translates the commands for the Roman pot low-level controls. *Details in the next talk...*

One **main difference** w.r. to collimators:
Roman pots accept **discrete settings only**. **No functions of time!**


Meetings started at the end of last year to follow up these aspects.


*Integration tests done at the Roman pot control test stand in bld. 187
(Mathias, Sylvain, Ivan and myself)*





Results on integration tests, Feb. 09

Two V pots moved for the first time with the CCC application!






Basic positioning tests







Tests of interlock limits




Set tight tolerance thresholds of 200 microns (warning levels at 100 μm).

Small movements within OP limits.


Checked that settings outside thresholds are REJECTED.






Feedback from first integration test

- For a vertical unit with two pots, we could test successfully:
 - Definition of position settings by the top level. Transmission to the PXI through the FESA layer.
Movements of the Roman pots as specified!
 - Response of **switches** for the OUT positions (monitoring other switches not yet operational)
 - Verification of the **ARMING/DISARMING mechanisms** (operator requests + monitoring)
 - **Trigger** of movements via software trigger.
 - **STOP** functionality.
 - Precise movements below **50 microns**, within OP defined thresholds.
 - Definition of **discrete interlock limits** by the top level. Transmission to the PXI through FESA.
 - Zero-th order **check of machine protection tests**: rejection of position settings outside limits.
- List of follow-ups:
 - Implementation of monitoring of all switch statuses → Done: ready for tests
 - Updated GUIs for Roman pots specific features → First prototype ready
 - Implements appropriate FESA exceptions → Done: ready for tests
 - Optimize reaction time of software trigger → Done: ready for tests
 - Minor mistakes of variable assignments for limits (readout only) → Ongoing.
- Not addressed yet:
 - Protection of settings from unauthorized changes (Role-based access, RBAC, aspects)
 - Full integration into the LSA TRIM application (**Done: ready for tests**)
 - Finalize list of hardware alarms, warning and errors
 - Trigger by hardware timing (not yet decided)



Outline

- Introduction**
- Results of integration tests**
- Status of CCC applications**
- Conclusions**



Updated RP application

LHC Collimator Control Application - LHC beam commissioning (Device: "XRPV.187.TEST")

Jaw corners Increment

Set single motor positions

TOP (LU) [mm] 0.0 Apply!

CANCEL last

STOP all!

BOTTOM (RU) [mm] 0.0 Out switches

Initialization

TOP (LU) UP-IN UP-OUT
BOTTOM (RU) UP-IN UP-OUT

Positions readout from the low-level

LVDT's Left UP dflt aa Gap UP dflt ee
Jaw edges Left DW dflt bb Gap DW dflt ff
Right UP dflt cc Centre UP dflt TT
Right DW dflt dd Centre DW dflt FF

Display jaw: TOP (LU) BOTTOM (RU)

Positions: Set LVDT Warn Lim Res Motor

BLM: BLM 1 BLM 2 BLM 3 BLM 4 LogY

Views Beam loss data [25/04/09 16:43:54]

Beam loss signal [a.u.]

1.0E0
8.0E-1
6.0E-1
4.0E-1
2.0E-1
0.0E0
-2.0E-1
-4.0E-1
-6.0E-1
-8.0E-1
-1.0E0

16:41:40 16:42:00 16:42:20 16:42:40 16:43:00 16:43:20 16:43:40

Jaw positions [25/04/09 16:41:48]

Jaw positions [mm]

1.00
0.80
0.60
0.40
0.20
0.00
-0.20
-0.40
-0.60
-0.80
-1.00

16:41:40 16:42:00 16:42:20 16:42:40 16:43:00 16:43:20 16:43:40


time [hh:mm:ss]

Needs further little improvements/tuning with users, but basic requirements available

Console

```
--> BLMEI.4L5.B1I1_TCTVA.4L5.B1
--> BLMES.4L5.B1I1_TCTVA.4L5.B1
```

16:42:05 - Ready.



LSA-TRIM implementation

Setting generation and storage in OP database

Trim Editor

RBA: stefano LHC OP BP

Parameter selection - LHCRING

System Type Groups Parameters Fields

RF_NOT_USED	XRPV.187.TEST/InterlockThresholdFunct	warning_inner_right_upstream
ROMAN POTS	XRPV.187.TEST/RequiredAbsPositionFunct	warning_outer_gap_downstream
SECTOR45		
SECTOR56		
SECTOR67		
SECTOR_23		
SEPARATION/RECOMBINATION		
SMP		
SPS FREQUENCY		
SQEW QUADRUPOLE		
SQEW SEXTUPOLES		
TRIPLET CORRECTION		
TRIPLETS		

Select All Select All

Setting part: Value Target Correction Trim History Time base:

Parameter	Value	Time base
XRPV.187.TEST/InterlockThresholdFunct#dump_inner_left_upstream	10.336428066964077	RAMP_5TeV_V2@0,[START]
XRPV.187.TEST/InterlockThresholdFunct#dump_inner_right_upstream	-10.336347883004995	
XRPV.187.TEST/InterlockThresholdFunct#dump_outer_left_upstream	11.424473147675007	
XRPV.187.TEST/InterlockThresholdFunct#dump_outer_right_upstream	-11.424384481238176	
XRPV.187.TEST/InterlockThresholdFunct#warning_inner_left_upstream	10.717243844530314	
XRPV.187.TEST/InterlockThresholdFunct#warning_inner_right_upstream	-10.717160693069198	
XRPV.187.TEST/InterlockThresholdFunct#warning_outer_left_upstream	11.043657368736604	
XRPV.187.TEST/InterlockThresholdFunct#warning_outer_right_upstream	-11.043571672546143	
XRPV.187.TEST/RequiredAbsPositionFunct#left_upstream	10.880450606565605	
XRPV.187.TEST/RequiredAbsPositionFunct#right_upstream	-10.880366182875525	

Cancel Last Trim

Trim Editor

RBA: stefano LHC OP BP

Parameter selection - LHCRING

System Type Groups Parameters

RF_NOT_USED	XRPV.187.TEST/BBCentre	
ROMAN POTS	XRPV.187.TEST/BBParam	
SECTOR45		
SECTOR56		
SECTOR67		
SECTOR_23		
SEPARATION/RECOMBINATION		
SMP		
SPS FREQUENCY		
SQEW QUADRUPOLE		
SQEW SEXTUPOLES		
TRIPLET CORRECTION		
TRIPLETS		


Select All Select All

Setting part: Value Target Correction Trim History Time base:

Parameter	Value	Time base
XRPV.187.TEST/BBCentre	0.0	RAMP_5TeV_V2@0,[START]
XRPV.187.TEST/BBParam#sigma_x	0.76103531877731	
XRPV.187.TEST/BBParam#sigma_xp	0.009591811659307918	
XRPV.187.TEST/BBParam#sigma_y	1.0880408394720564	
XRPV.187.TEST/BBParam#sigma_yp	0.008422397080899058	

Show Field(s) Hierarchy Trim period Trim

Definition of settings in beam size units w.r. to local beam orbit, like the other collimators




Configuration / RP names

										<i>Official LHC Layout names</i>	<i>"display" name for communication</i>
										<i>TOTEM names</i>	
CMS relative	Roman Pot Product Breakdown Structure	Roman Pot order	RP mechanical design name	LHC layout name	Collimator application name	Roman Pot position	Left up	Right up	Collimator ID (index)	CCC name	CCC "expert" name
	EDMS 906715	EDMS 901060			EDMS 934341		EDMS 934341	EDMS 934341	EDMS 934341		
Left	tot.Rp.45.220.fr.hr	3	Station 3	XRPT1.6L5.B2	XRPTOT04	Horizontal			0	XRPH.B6L5.B2	XRPT1.6L5.B2-XRPTOT04
	tot.Rp.45.220.fr.tp	1			XRPTOT05	Vertical up			1	XRPV.B6L5.B2	XRPT1.6L5.B2-XRPTOT05/06
	tot.Rp.45.220.fr.bt	2			XRPTOT06	Vertical down					
	tot.Rp.45.220.nr.hr	4	Station 3	XRPT2.6L5.B2	XRPTOT10	Horizontal			2	XRPH.A6L5.B2	XRPT2.6L5.B2-XRPTOT10
	tot.Rp.45.220.nr.tp	5			XRPTOT07	Vertical up			3	XRPV.A6L5.B2	XRPT2.6L5.B2-XRPTOT07/11
	tot.Rp.45.220.nr.bt	6			XRPTOT11	Vertical down					
	tot.Rp.45.147.fr.hr	9	Station 1	XRPT1.4L5.B2	XRPTOT12	Horizontal			4	XRPH.B4L5.B2	XRPT1.4L5.B2-XRPTOT12
	tot.Rp.45.147.fr.tp	7			XRPTOT14	Vertical up			5	XRPV.B4L5.B2	XRPT1.4L5.B2-XRPTOT14/13
	tot.Rp.45.147.fr.bt	8			XRPTOT13	Vertical down					
	tot.Rp.45.147.nr.hr	10	Station 1	XRPT2.4L5.B2	XRPTOT15	Horizontal			6	XRPH.A4L5.B2	XRPT2.4L5.B2-XRPTOT15
	tot.Rp.45.147.nr.tp	11			XRPTOT09	Vertical up			7	XRPV.A4L5.B2	XRPT2.4L5.B2-XRPTOT09/08
	tot.Rp.45.147.nr.bt	12			XRPTOT08	Vertical down					
Right	tot.Rp.56.147.nr.hr	15	Station 1	XRPT1.4R5.B1	XRPTOT25	Horizontal			8	XRPH.A4R5.B1	XRPT1.4R5.B1-XRPTOT25
	tot.Rp.56.147.nr.tp	13			XRPTOT27	Vertical up			9	XRPV.A4R5.B1	XRPT1.4R5.B1-XRPTOT27/26
	tot.Rp.56.147.nr.bt	14			XRPTOT26	Vertical down					
	tot.Rp.56.147.fr.hr	16	Station 1	XRPT2.4R5.B1	XRPTOT23	Horizontal			10	XRPH.B4R5.B1	XRPT2.4R5.B1-XRPTOT23
	tot.Rp.56.147.fr.tp	17			XRPTOT28	Vertical up			11	XRPV.B4R5.B1	XRPT2.4R5.B1-XRPTOT28/22
	tot.Rp.56.147.fr.bt	18			XRPTOT22	Vertical down					
	tot.Rp.56.220.nr.hr	21	Station 3	XRPT1.6R5.B1	XRPTOT24	Horizontal			12	XRPH.A6R5.B1	XRPT1.6R5.B1-XRPTOT24
	tot.Rp.56.220.nr.tp	19			XRPTOT17	Vertical up			13	XRPV.A6R5.B1	XRPT1.6R5.B1-XRPTOT17/20
	tot.Rp.56.220.nr.bt	20			XRPTOT20	Vertical down					
	tot.Rp.56.220.fr.hr	22	Station 3	XRPT2.6R5.B1	XRPTOT16	Horizontal			14	XRPH.B6R5.B1	XRPT2.6R5.B1-XRPTOT16
	tot.Rp.56.220.fr.tp	23			XRPTOT19	Vertical up			15	XRPV.B6R5.B1	XRPT2.6R5.B1-XRPTOT19/18
	tot.Rp.56.220.fr.bt	24			XRPTOT18	Vertical down					

Detailed mapping of device names worked out.

Will provide both names every time to be sure that there are no communication errors...

Need to be EXTREMELY careful!!!



OP database for HW parameters

<http://lhc-operation.web.cern.ch/lhc-operation/collimator/LHCCollimatorOPdatabase.asp>

The screenshot shows the LHC Collimation Project homepage. It includes a logo, navigation links (Top, Project Team, Notes, Collimator List, Sounds/Movies, Meetings, Links, Papers, Talks (WG), Layout IR3/7, AB Departm., Pictures), and a section titled "Collimator operational information". Below this are two tables: "Select by IP" and "Select collimators Family".

Select by IP			Select collimators Family		
IP/BEAM	B1	B2	FAMILY	TCP	TCLP
1	X	X	TCSG	INJP	
2	X	X	TCLA	TCDI	
3	X	X	TCT	TCDQ	
5	X	X	OTHERS	XRP	
6	X	X			
7	X	X			
8	X	X			
TI	X	X			
ALL	X	X			

Template for collimator HW parameters

CERN name (MTF) CERCA name MADX name	HCTCT_001-CQ000316 TCT_065 TCLA.7R3.B1
ID Angle Material Length Beam Family IP	1013894 0.0 W 1.0 B1 TCLA 3
BLMI BLMS	BLMEI.7R3.B1I1_TCLA.7R3.B1 BLMES.7R3.B1I1_TCLA.7R3.B1
Jaw corner notation	LEFT UP B LEFT DOWN D RIGHT UP A RIGHT DOWN C
	AXIS LEFT UP 1 AXIS LEFT DOWN 1 AXIS RIGHT UP 1 AXIS RIGHT DOWN 1 AXIS TANK 0
Mechanical STOPS	LEFT UP 29.9806 OUT -6.0609 IN LEFT DOWN 29.9867 OUT -6.0624 IN RIGHT UP -30.0021 OUT 6.0435 IN RIGHT DOWN -29.9979 OUT 6.0441 IN ANTI - UP 0.6339 OUT ANTI - DOWN 0.6293 IN
Switches	LEFT UP 29.3256 OUT -5.3839 IN LEFT DOWN 29.3327 OUT -5.3984 IN RIGHT UP -29.3541 OUT 5.3875 IN RIGHT DOWN -29.3359 OUT 5.3841 IN ANTI - UP 0.7469 OUT ANTI - DOWN 0.7393 IN
Maximum flatness error	Left: -0.0334 AC: 0.0412 Right: 0.0412 BD: 0.0334
Mechanical plays	Left: 0.0180 A: 0.0080 Left: DOWN 0.0150 B: 0.0180 Right: UP 0.0080 C: 0.0070 Right: Down 0.0070 D: 0.0150
Auto-retraction	Left: UP 0.0070 A: 0.0040 Left: DOWN 0.0030 B: 0.0070 Right: UP 0.0040 C: 0.0050 Right: Down 0.0050 D: 0.0030
Maximum tilt angle	Left: Plus 3.00 AC: Plus 3.0000 Left: Minus 3.00 AC: Minus 3.0000 Right: Plus 3.00 BD: Plus 3.0000
Measurements in the metrology frame:	Mechanical stops Switches Maximum flatness error (mm) Mechanical plays Auto-retraction Maximum tilt angle
Mechanical stops	A: -30.0021 OUT 6.0435 B: 29.9806 OUT -6.0609 C: -29.9979 OUT 6.0441 D: 29.9867 OUT -6.0624
Switches	A: 29.3541 OUT 5.3875 B: 29.3256 OUT -5.3839 C: 29.3359 OUT 5.3841 D: 29.3327 OUT -5.3984
Maximum flatness error (mm)	AC: 0.0412 BD: 0.0334
Mechanical plays	A: 0.0080 B: 0.0180 C: 0.0070 D: 0.0150
Auto-retraction	A: 0.0040 B: 0.0070 C: 0.0050 D: 0.0030
Maximum tilt angle	AC: Plus 3.0000 B: Minus 3.0000 C: Minus 3.0000 D: Plus 3.0000
Mechanical stops	Max gap AB: 59.9827 CD: 59.9845
Switches	Max gap AB: 0.6339 CD: 0.6293
Maximum flatness error (mm)	Max gap AB: 58.6797 CD: 58.6685
Mechanical plays	Min gap AB: 0.7469 CD: 0.7393
Auto-retraction	Min gap AB: 0.0050 CD: 0.0030
Maximum tilt angle	AC: Plus 3.0000 BD: Minus 3.0000

ELEMENT_NAME	MTF links	FAMILY	IP	BEAM	ANGLE	Jaw Orientation	Summary	Photo 252	Photo LH
TCLA.7L3.B2	+HCTCT_001-CQ000315 +Acceptance +ProDB	TCLA	IP3	B2	0.0	B/D/A/C	xls/pdf		
TCLA.6L3.B2	+HCTCT_001-CQ000313 +Acceptance +ProDB	TCLA	IP3	B2	0.0	B/D/A/C	xls/pdf		
TCLA.B5L3.B2	+HCTCT_001-CQ000318 +Acceptance +ProDB	TCLA	IP3	B2	0.0	B/D/A/C	xls/pdf		

Input expected from TOTEM: provide the **mechanical references** for the OP database (switch positions, mechanical references, mechanical plays, ...)
BD tables ready to be filled!

ELEMENT_NAME	MTF links	FAMILY	IP	BEAM	ANGLE	Jaw Orientation	Summary	Photo 252	Photo LHC	3D Layout
XRPV.B6L5.B2	+Unknown-Roman-Pot19 +Acceptance +ProDB	XRPV	IP5	B2	90.0	///	xls/pdf			
XRPH.B6L5.B2	+Unknown-Roman-Pot20 +Acceptance +ProDB	XRPH	IP5	B2	0.0	///	xls/pdf			
XRPH.A6L5.B2	+Unknown-Roman-Pot21 +Acceptance +ProDB	XRPH	IP5	B2	0.0	///	xls/pdf			
XRPV.A6L5.B2	+Unknown-Roman-Pot22 +Acceptance +ProDB	XRPV	IP5	B2	90.0	///	xls/pdf			
XRPV.B4L5.B2	+Unknown-Roman-Pot23 +Acceptance +ProDB	XRPV	IP5	B2	90.0	///	xls/pdf			
XRPH.B4L5.B2	+Unknown-Roman-Pot24 +Acceptance +ProDB	XRPH	IP5	B2	0.0	///	xls/pdf			
XRPH.A4L5.B2	+Unknown-Roman-Pot25 +Acceptance +ProDB	XRPH	IP5	B2	0.0	///	xls/pdf			



Logging of Roman pot positions

Sign In Data Source preferences: LDB (PRO->TEST) -> MDB (PRO->DEV) Elapsed: 239ms

Query Output Query Variable Hierarchies Variable Search Variable Lists Settings About

Hierarchy Variable Selection

- ▼ ▷ ROOT
 - ● ADE
 - ● ATLAS
 - ● CMS
 - ● CNGS
 - ● COLLIMATOR
 - ● CRYO
 - ● CTF3
 - ● Fundamental Data
 - ● LEIR
 - ▼ ▷ LHC
 - ● BLM
 - BPM
 - ● Beam Instrumentation
 - ● Beam Interlocks
 - ● Beam dump
 - ▼ ▷ Collimators
 - ▼ ▷ Positions
 - ▼ ▷ B1
 - ▼ ▷ IP1
 - ● TCL
 - ▼ ▷ TCTH
 - DiscreteSettings
 - DiscreteThresholds
 - FunctionSettings
 - FunctionThresholds
 - MeasuredCornerPositions
 - MeasuredVerticalQuota
 - QuotaSettings
 - Status
 - expertMDCDiagnostics
 - expertPRSDiagnostics
 - ● TCTV
 - ● IP2
 - ● IP3
 - ● IPS
 - ● IP6
 - ● IP7
 - ● IP8
 - ● B2
 - ● Temperatures
 - ● Kickers
 - ● MD
 - ● Power Converters
 - ● Powering Interlocks
 - ● RF
 - ● Radiation
 - ● Warm Interlocks
 - ● LHC HWC
 - ● LHCBLM

Variable Filters

Name: % Type: %

Search Results

Variable Name	De...	Unit	Datatype
TCTH.4L1.B1:MEAS_LIMIT_DUMP_INNER_GD	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LIMIT_DUMP_INNER_GU	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LIMIT_DUMP_INNER_LD	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LIMIT_DUMP_INNER_LU	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LIMIT_DUMP_INNER_RD	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LIMIT_DUMP_INNER_RU	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LIMIT_DUMP_OUTER_GD	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LIMIT_DUMP_OUTER_GU	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LIMIT_DUMP_OUTER_LD	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LIMIT_DUMP_OUTER_LU	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LIMIT_DUMP_OUTER_RD	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LIMIT_DUMP_OUTER_RU	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LIMIT_WARN_INNER_GD	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LIMIT_WARN_INNER_GU	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LIMIT_WARN_INNER_LD	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LIMIT_WARN_INNER_LU	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LIMIT_WARN_INNER_RD	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LIMIT_WARN_INNER_RU	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LIMIT_WARN_OUTER_GD	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LIMIT_WARN_OUTER_GU	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LIMIT_WARN_OUTER_LD	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LIMIT_WARN_OUTER_LU	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LIMIT_WARN_OUTER_RD	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LIMIT_WARN_OUTER_RU	Val...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LVDT_GD	LV...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LVDT_GU	LV...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LVDT_LD	LV...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LVDT_LU	LV...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LVDT_RD	LV...	mm	NUMERIC
TCTH.4L1.B1:MEAS_LVDT_RU	LV...	mm	NUMERIC
TCTH.4L1.B1:MEAS_MDCERRORS	Err...		NUMERIC
TCTH.4L1.B1:MEAS_MDCSTATE	Stat...		NUMERIC
TCTH.4L1.B1:MEAS_MDCWARNINGS	War...		NUMERIC
TCTH.4L1.B1:MEAS_MOTOR_LD	Mot...	mm	NUMERIC
TCTH.4L1.B1:MEAS_MOTOR LU	Mot...	mm	NUMERIC
TCTH.4L1.B1:MEAS_MOTOR RD	Mot...	mm	NUMERIC
TCTH.4L1.B1:MEAS_MOTOR RU	Mot...	mm	NUMERIC
TCTH.4L1.B1:MEAS_PROFILE_TIME	Tim...	ns	NUMERIC
TCTH.4L1.B1:MEAS_PROFILE_WIDE	F...		NUMERIC

Ready to define the same logging structure for the Roman pots.

Implementation by R. Billen, C. Roderick


Will save:

- Requested settings for positions
 - Requested settings for interlocks
 - Statuses

Additional requirements?

E.g.: for the collimators we also save expert properties for diagnostics purposes...

Post-mortem requirements?



Conclusions

We have set-up a nice working environment for testing the various aspects related to the Roman pot controls

First controls integration tests were very **successful**:

- Profited from the availability of the controls test stand on surface.
- 3-tier controls architecture deployed and fully tested: saw the first RP movements!
- Could set thresholds with the CCC application. Preliminary checks done.

What comes next:

- Follow-up open issues. Configure the 2009 system (24 pots).
- More integration tests on surface - ToDo s being followed-up:
Web-based tracing of issues at <https://savannah.cern.ch/projects/rpcs>
- Remote commissioning of the system and machine protection tests
(will take inspiration from the validation tests developed for collimators).

What we expect from TOTEM:

- Provide HW parameters for OP database for all the pots of the 2009 system
- Handle the critical calibration data (discussed in the next talk)
- HW commissioning in the tunnel, in particular machine protection functionality
- Provide OP with the final set of “as-installed” operational parameters
- Clarify procedures for the communication with the CCC...

Still a lot of work ahead...